

**SALEM COUNTY IMPROVEMENT AUTHORITY**

**RESOLUTION 2018-38**

**April 12, 2018**

**RESOLUTION OF THE SALEM COUNTY IMPROVEMENT AUTHORITY  
AUTHORIZING AWARD OF QUOTE FOR PAVING WORK AT  
THE SCALE HOUSE TO RICKY SLADE CONSTRUCTION, INC.**

**WHEREAS**, The Salem County Improvement Authority ("SCIA") has a need for excavating, supplying and installing asphalt at the scale house; and

**WHEREAS**, Ricky Slade Construction, Inc. ("Slade") has submitted a quote for said asphalt work; and

**WHEREAS**, SCIA finds the quote from Slade to be acceptable and desires to award the quote to Slade; and

**NOW, THEREFORE, BE IT RESOLVED** that the award of the quote for excavation, supply and installation of asphalt at the scale house to Slade.


ATTEST:

  
\_\_\_\_\_  
Barry Davis, Secretary

  
\_\_\_\_\_  
Cordy Taylor, Chairman

**CERTIFICATION**

I hereby certify the above to be a true copy of a resolution adopted by the Salem County Improvement Authority Board at their regular meeting held April 12, 2018.

  
\_\_\_\_\_  
Barry Davis, Secretary

# Proposal

## RICKY SLADE CONSTRUCTION, INC.

54 Slade Lane • Bridgeton, NJ 08302

Telephone: (856) 455-4046 • Fax: (856) 455-8380

PROPOSAL SUBMITTED TO SCIA/Solid Waste Division	PHONE 856-935-7900 ex17	FAX 856-935-7331	DATE April 5, 2018
STREET 52 McKillip Road	JOB NAME Driveway Proposal		
CITY, STATE, ZIP CODE Alloway NJ 08001	JOB LOCATION		
DATE OF PLANS	REVISED DATE	ATTENTION Juley Acton email: Jacton@scianj.org	

We hereby submit specifications and estimates for:

Option 1: 168' x 12' from gate to scale

Saw cut existing asphalt where needed, to provide smooth transition.

Excavate existing Asphalt to a depth of 12".

Supply & Install 6" +/- of DGA (Crushed Concrete)

Fine, Grade, Compact sub base

Supply & Install 4" 1-2 Stab base.

Supply & Install 2" 1-4 Commercial top Mix.

Within Approx area measuring 224 sq. yds. At \$43.00 per Sq. Yd.

9,632.00

Option 2: 360'x12' Scale to 2nd entrance

Saw cut existing asphalt where needed, to provide smooth transition.

Excavate existing Asphalt to a depth of 12".

Supply & Install 6" of DGA

Fine, Grade, Compact sub base

Supply & Install 4" 1-2 Stab base.

Supply & Install 2" 1-4 Commercial top Mix.

Within Approx area measuring 480 sq. yds. At \$43.00 per Sq. Yd.

20,640.00

Option 3: 50'x40' Potholes

Saw cut existing asphalt where needed, to provide smooth transition.

Excavate existing Asphalt to a depth of 12".

Supply & Install 6" of DGA

Fine, Grade, Compact sub base

Supply & Install 4" 1-2 Stab base.

Supply & Install 2" 1-4 Commercial top Mix.

Within Approx area measuring 223 sq. yds. At \$43.00 per Sq. Yd.

9,589.00